

## Rig

Skytop Twin Steer/Tri Drive  
Detroit Diesel 60 Series  
Allison 5860 transmission  
42" X 10" Main Drum  
38" X 8" Sandline Drum  
Kobelt Disk Brake  
Crown Saver  
1,612 Hrs on Level IV Recertification



## Mast

104' Freestanding (No anchors)  
225,000 # Telescopic Mast

## BOP's

7 1/16" Double Gates and Annular  
5000# Working Pressure

## Rig Pump

Carrier Style Twin Steer/Tandem Drive  
5 X 5 Triplex SJ 300  
5000# Working Pressure  
Detroit Diesel 8V-71 360HP  
Allison 750 transmission



## Rig Tank

Skidded  
225 BBL  
Trough  
Degasser  
Line Pipe 5000# Working Pressure

## Tool Truck Carrier

Carrier Style Single Steer/Tandem Drive  
Detroit Diesel 8V-71 360HP  
Allison 750 transmission

## Crew Accumulator Generator Trailer

30' Mobile  
Class 3 Accumulator  
65 KW Generator  
Potty  
Change Room



## Additional Equipment Included

Equipped With Installed Lighting Throughout Derrick For Night Time Operations  
Engineered Freestanding - No Anchors Required  
2-Self Retracting Lifelines  
Standpipe Rated For 5,000#  
Escape Line, Escape Buggy With Monkeyboard Rear Egress  
Annular API 16A 7 1/16", 5,000# Working Pressure  
Double Gate API 16A (Pipe Rams, Blind Rams) 7 1/16", 5,000# Working Pressure  
60 Gal 3 Station Accumulator With Electric Pump And Nitrogen Backup  
Remote 3 Station Actuator  
Fire Rated BOP Hoses  
2 7/8" TIW Valve  
Hydraulic Bag Type Rod BOP  
Slips                      Air Actuated, 100ton - 2 3/8" - 3 1/2"  
                                 Stripping Rubber Housing  
Tongs                      58-93  
                                 Air Actuated Backups  
                                 Hydraulic Lift Cylinder  
                                 Accepts 2 3/8" - 3 1/2" Dies  
Tubing Elevators      API Spec 8A/8C 2 3/8" 100 Ton  
                                 API Spec 8A/8C 2 7/8" 100 Ton  
Sucker Rods            4-API Spec 8A/8C Rod Elevator 37.5 Ton  
                                 API Spec 8A/8C 37.5 Ton Rod Hook  
                                 3/4" - 1" Elevator Inserts  
                                 2-3/4" 7/8" Rod Wrenchs  
                                 2-1" Rod Wrenchs  
Traveling Blocks      100 ton API 8C 1" Drill Line Sheves  
Bale Links              API 8C 72", 150 ton  
Saverhead              Double Rubber  
Lubricator              3" X 25'  
Sinker Bars             2- 10'  
Mandrels                Knucle, Top And Lower Mandrel 2 3/8", 2 7/8", 3 1/2"  
Centrifuge  
Complete With All Hand Tools  
400' = 2" X 5,000# Line Pipe  
2" X 5,000# Chicksans  
2" X 5,000# Kelly Hoses  
4" Suction Hoses  
Mud Scale  
First Aid Kit  
Stretcher  
4 Fire Extinguishers  
Eye Wash Station  
Derrick Belt  
Clipper Type Drill Line Weight Indicator  
2 Self Contained Breathing Apparatus  
High Angle Rescue Kit  
Spill Kit